

SECTION 1 - TECHNICAL METHOD STATEMENT

Tender Reference: SYN/WORKS/2026/099

Bidder: Nsereko Engineering Services (fictional entity)

The works will be executed in four phases. Site clearance and setting out will be completed in week one. Excavation to formation level will follow, with spoil removed to the approved tip. Blinding and reinforcement will be inspected before any concrete is poured. Curing will be maintained for seven days under damp hessian.

SECTION 2 - PROPOSED CONSTRUCTION PROGRAMME

Phase 1	Site establishment and clearance	Weeks 1 to 2
Phase 2	Substructure and foundations	Weeks 3 to 9
Phase 3	Superstructure and roofing	Weeks 10 to 20
Phase 4	Finishes, testing and handover	Weeks 21 to 26

Float of three weeks has been allowed against the rainy season. The critical path runs through the substructure works.

SECTION 3 - PLANT AND EQUIPMENT SCHEDULE

- 1 excavator, 20 tonne, owned
- 2 tipper trucks, 10 cubic metres, owned
- 1 concrete mixer, 500 litre, owned
- 1 poker vibrator, owned
- 1 water pump, 3 inch, to be hired
- Scaffolding, 400 square metres, to be hired

All owned plant is serviced quarterly by the manufacturer's agent.

SECTION 4 - KEY PERSONNEL

Site Agent, twelve years of experience in building works.

Site Engineer, eight years of experience, degree in civil engineering.

Foreman, fifteen years of experience in reinforced concrete.

Safety Officer, part time, five years of experience.

Curricula vitae are held on file and can be produced on request.

SECTION 5 - HEALTH AND SAFETY APPROACH

Personal protective equipment will be issued to all site personnel. A daily briefing will be held before work begins. Excavations deeper than one point two metres will be shored and barricaded. A first aid box and a trained first aider will be present on site at all times. Accidents will be recorded in the site register and reported to the supervising officer within twenty four hours.